

N1 – BELA-BELA TO PIENAARSRIVIER (US2)

LIMPOPO

PROJECT TYPE: ROADWORKS

CLIENT:

Northern Toll Road Ventures

VALUE:

R364.7 million

CONSULTANTS:

AECOM (Pty) Ltd

PROJECT DURATION:

16 months

DATE OF PROJECT:

July 2015 – October 2016

PROJECT DESCRIPTION:

The project forms part of the Bakwena Platinum Corridor Concessionaire stretching between Pienaarsrivier Interchange and Bela-Bela Interchange. The total contract length is 57.4km of carriage way.

The rehabilitation consists of:

- Recycling the existing pavement layer (8 783 m³)
- Pave 70mm of BTB (33 528 ton)
- Pave 40mm of asphalt surfacing (197 348 m²)
- Application of texture slurry (4 320 m³)
- 13.2mm bitumen rubber seal using pre-coated chips (2 718 594 m²)
- All road markings, barriers and road studs shall be reinstated.
- Installations of open concrete drains (61.5 m³)

